

MYSORE CITY IMPROVEMENT TRUST BOARD.

Dated 21st February 1904.

Notice is hereby given that sealed tenders will be received at the office of the Chairman of the Board of Trustees for the Mysore City Improvements, up to 15th March 1904, for the construction of drains and works relating to them. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1904.

2. The plans, detailed estimate and conditions may be seen at the office of the Chairman of the Board of Trustees for the Mysore City Improvements at Mysore, between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman's office. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory Notes, as earnest money, and be superscribed "Tender for the drainage of No. 1 drainage area of Mysore City," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Trustees for the improvement of the Mysore City, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the quantity of work to be done in No. 1 Drainage area of Mysore City.

| No. | Items of work. | Per. | Approximate quantity. |
|-----|---|----------|-----------------------|
| 1 | Earthwork excavation for constructing open drains, etc. | C. yds. | 5,298 |
| 2 | Machine-ground surki mortar concrete for constructing drains | C. ft. | 79,974 |
| 3 | Machine-ground surki mortar plastering for drains. | Sqr. | 1,411.47 |
| 4 | Cement plastering for drains | Sqr. | 1,411.47 |
| 5 | Machine-ground surki mortar concrete for filling foundation, for silt traps etc. | C. ft. | 3,683 |
| 6 | Burnt brick in machine-ground surki mortar for silt traps | do | 28,627 |
| 7 | Machine-ground surki mortar plastering for silt traps | Sqr. | 322.92 |
| 8 | Burnt stone slabs 3" to 4½" thick for covering drains | S. ft. | 10,723 |
| 9 | Do 2½" to 3" thick | do | 338 |
| 10 | Laying of stoneware glazed pipe 4" dia., including excavation and refilling for an average depth of 4' (when pipes are supplied.) | R. ft. | 2,840 |
| 11 | Laying of stoneware glazed pipe 9" dia. | do do do | 250 |
| 12 | Coping with burnt brick in mortar and plastering | do | 1,376 |
| 13 | Arch work in burnt brick in machine-ground surki mortar | C. ft. | 53 |
| 14 | Teakwood door (3'x6') including frame to the washing platform at latrines. | Each | 16 |

N. B.—Materials for construction of drains, viz., broken metal of size specified, burnt lime and burnt brick powder (surki), may be tendered for separately for delivery in any part of the area comprised.

Machinery for grinding surki mortar will be made available, the tenderer bearing the charges for the preparation of the mortar.

Dated 21st February 1904.

Notice is hereby given that sealed tenders will be received at the office of the Chairman of the Board of Trustees for the Mysore City Improvement Division, up to 15th March 1904, for the construction of drains and works relating to them. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1904.

2. The plans, detailed estimate and conditions may be seen at the office of the Chairman of the Board of Trustees for the Mysore City Improvements, Mysore, between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman's office. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory Notes, as earnest money, and be superscribed "Tender for constructing drains and works connected therewith in Nazarbada," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Trustees for the Improvement of the Mysore City, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the quantity of drainage works to be done in Nazarbad.

| No. | Items of work. | Per | Approximate quantity. |
|-----|--|---------|-----------------------|
| 1. | Earth work excavation for constructing open drains, etc. | C. yds. | 3,584 |
| 2. | Machine-ground surki mortar concrete for constructing drains | C. ft. | 48,279 |
| 3. | Machine-ground surki mortar plastering for drains | Sqr. | 838.71 |
| 4. | Cement plastering for drains | Sqr. | 838.71 |
| 5. | Machine-ground surki mortar concrete for filling foundation of silt-traps, storm-overflows and manholes, etc. | C. ft. | 6,495 |
| 6. | Burnt brick in machine-ground surki mortar do | C. ft. | 22,226 |
| 7. | Machine-ground surki plastering for silt-traps, storm-overflows and manholes, etc. | Sqr. | 274.36 |
| 8. | Coping with burnt brick in mortar and plastering | R. ft. | 1,032 |
| 9. | Burnt stone slabs, 3" to 4 1/2" thick for covering drains | S. ft. | 3,440 |
| 10. | Do do 6" do | S. ft. | 80 |
| 11. | Laying of stoneware glazed pipes (4" diameter) including excavation and refilling for an average depth of 4 feet. (Note—Pipes will be supplied.) | R. ft. | 800 |
| 12. | Do do (6" diameter) do | R. ft. | 6,035 |
| 13. | Teakwood door with frame (3' x 6') to the washing platform at latrines | Each | 12 |

N.B.—Materials for construction of drains, viz., broken metal of size specified, burnt lime and surki brick powder, may be tendered for separately for delivery in any part of the area comprised.

It is to be noted that machinery for grinding mortar will be made available, the tenderer bearing the charges for the preparation of the mortar.

Dated 20th February 1904.

Notice is hereby given that sealed tenders will be received at the office of the Chairman of the Board of Trustees for the Mysore City Improvements, up to 15th March 1904, for the construction of drains and works appertaining thereto. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1904.

2. The plans, detailed estimate and conditions may be seen at the office of the Chairman of the Board of Trustees for the Mysore City Improvements at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman's office. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing drains and works appertaining thereto in Ittigegud," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Trustees for the Improvement of the Mysore City, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the quantity of drainage works to be done in Ittigegud.

| No. | Items of work. | Per | Approximate quantity. |
|-----|--|---------|-----------------------|
| 1 | Earthwork excavation for constructing open drains etc. | C. yds. | 6,122 |
| 2 | Machine-ground surki mortar concrete for constructing drains | C. ft. | 16,951 |
| 3 | Do do plastering for drains | Sqr. | 324.15 |
| 4 | Cement plastering for drains | do | 324.15 |
| 5 | Machine-ground surki mortar concrete for filling foundation of silt traps, storm overflows, etc. | C. ft. | 5,355 |
| 6 | Burnt brick in machine-ground surki mortar do | do | 14,851 |
| 7 | Machine-ground surki mortar plastering for silt traps, storm overflows, etc. | Sqr. | 182.73 |
| 8 | Burnt stone slabs 3" to 4½" thick for covering drains | S. ft. | 1,776 |
| 9 | Do do do do do do do do do do | do | 21 |
| 10 | Laying of stoneware glazed pipes 6" diameter, including excavation and refilling an average depth of 4' (when pipes are supplied). | R. ft. | 10,498 |
| 11 | Laying of stoneware glazed pipes 8" do do do do do do do do do do | do | 800 |
| 12 | Coping with burnt brick in mortar and plastering | do | 688 |
| 13 | Teakwood doors (3' x 6') including frame to the washing platform at latrines. | Each | 8 |

N. B.—Materials for construction of drains, viz., broken metal of size required, burnt lime, and surki brick powder, may be tendered for separately for delivery in any part of the area comprised.

Machinery necessary for grinding surki mortar will be made available, the tenderer bearing the charges for the preparation of the mortar.

Notice, dated 21st February 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Chairman of the Board of Trustees for the Improvement of the City of Mysore, up to 15th March 1904, for the building of drains and other subsidiary works. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1904.

2. The plans, detailed estimate and conditions may be seen at the office of the Chairman of the Board of Trustees for the Mysore City Improvements at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman's office. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing drains and subsidiary works in Idga Extension of the Mysore City," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Trustees for the Improvement of the Mysore City, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the quantity of drainage works to be done in Idga Extension.

| No. | Items of work. | Per | Approximate quantity. |
|-----|---|---------|-----------------------|
| 1. | Earthwork excavation for constructing open drains, etc. | C. yds. | 1,761 |
| 2. | Machine-ground surki mortar concrete for constructing drains, etc. | C. ft. | 15,541 |
| 3. | Machine-ground surki mortar plastering for drains | Sqr. | 265.00 |
| 4. | Cement plastering for drains | Sqr. | 265.00 |
| 5. | Machine-ground surki mortar concrete for filling foundation of cisterns, etc. | C. ft. | 204 |
| 6. | Burnt brick in machine-ground surki mortar for cisterns, etc. | C. ft. | 612 |

| No. | Items of work. | Per | Approximate quantity. |
|-----|---|--------|-----------------------|
| 7. | Machine-ground surki mortar plastering for brick work | Sqr. | 10.20 |
| 8. | Burnt stone slabs 3" to 4½" for constructing drains with 1½ feet depth of excavation. | S. ft. | 4,340 |
| 9. | Burnt stone slabs 3" to 4½" for covering drains | S. ft. | 2,783 |

N. B.—Materials for construction of drains, viz., broken metal of specified size, burnt lime and burnt brick powder (surki), may be tendered for separately for delivery in any part of the area comprised.

Machinery for grinding surki mortar will be made available, the tenderer bearing the charges for the preparation of the mortar.

Dated 21st February 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Chairman of the Board of Trustees for the Improvement of the Mysore City, up to 15th March 1904 for the construction of drains and works relating to them. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1904.

2. The plans, detailed estimate and conditions may be seen at the office of the Chairman of the Board of Trustees for the Mysore City Improvements at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman's office. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing drains in Jalapuri Extension," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Trustees for the Improvement of the Mysore City, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the quantity of drainage works to be done in Jalapuri Extension.

| | Items of work. | Per | Approximate quantity. |
|-----|---|---------|-----------------------|
| 1. | Earthwork excavation for constructing open drains, etc. | C. yds. | 2,640 |
| 2. | Machine-ground surki mortar concrete for constructing drains | C. ft. | 29,055 |
| 3. | Machine-ground surki mortar plastering for drains | Sqr. | 482.76 |
| 4. | Cement plastering for drains | Sqr. | 482.76 |
| 5. | Machine-ground surki mortar concrete for filling foundation of cisterns, etc. | C. ft. | 336 |
| 6. | Burnt brick in machine-ground surki mortar for cisterns, etc. | " | 1,008 |
| 7. | Machine-ground surki mortar plastering for brick work | Sqr. | 14.00 |
| 8. | Burnt stone slabs 3" to 4½" for constructing drains with 1½ feet depth of excavation. | S. ft. | 7,750 |
| 9. | Burnt stone slabs 3" to 4½" for covering drains | " | 3,686 |
| 10. | Burnt stone slabs 2½" to 3" for putting to the sides of drains | " | 2,218 |

N. B.—Materials for construction of drains, viz., broken metal of specified size, burnt lime and burnt brick powder (surki) may be tendered for separately for delivery in any part of the area comprised.

Machinery for grinding surki mortar will be made available, the tenderer bearing the charges for the preparation of mortar.

D. SITARAM RAO,
Chairman of the Board of Trustees, Mysore.